

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 01	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				
Pay.gov Amount: \$145.00		Agency Tracking ID: EWL-APM-256194		Pay.gov Tracking ID: 27PT055H		
General Information						
API 043122016601		Approval Dt 31-JUL-2025		Approved By Bethram Ofole		
Submitted Dt 21-JUL-2025		Well Status Completed		Water Depth 700		
Surface Lease P00301		Area LB		Block 6488		
Approval Comments						
Conditions of Approval 1. All operations must be conducted in accordance with the OCS Lands Act (OCSLA), the lease terms and stipulations, the regulations of 30 CFR Part 250, Notices to Lessees and Operators (NTLs), the approved (revised) Application for Permit to Modify (APM/RPM), and any written instructions or orders of the District Manager or its designee. 2. A copy of this permit (including all attachments) must be kept on location and made available to inspectors upon request during the permitted operation. 3. All pressure-containing equipment must be tested to the approved permitted pressure and recorded on the daily operations report. If well pressures exceed the SITP/MASP stated in the approved permit, the equipment in use must be tested at a minimum to the new observed pressure. The District Manager or its designee must be immediately notified of this pressure change and, an RPM must be submitted to document the change. 4. Notify the Permitting Section at least 72 hours in advance of beginning these approved operations AND of any required BOP tests AND of any plug testing or tagging. You MUST NOT proceed with these operations until an inspector can arrive to witness the testing OR the Permitting Section Chief or their designee waives the witnessing. 5. WAR reports are due no later than noon each Wednesday.						
Correction Narrative						
Permit Primary Type Abandonment Of Well Bore						
Permit Subtype(s) Plugback To Sidetrack/Bypass						
☒ Proposed or ☐ Completed Work						
Operation Description Plug back wellbore to sidetrack						
Procedural Narrative The C-61 is currently shut in due to an ESP failure. Purpose of the workover is to Abandon the Lower Completion via Cement Retainer and Cement in preparation for a Whipstock Sidetrack out of the 9 5/8" Casing to sidetrack the wellbore.						
Subsurface Safety Valve Type Installed SCSSV Feet below Mudline 298 Maximum Anticipated Surface Pressure (psi) 1400 Shut-In Tubing Pressure (psi) Maximum Anticipated Wellhead Pressure (psi) 1400 Shut-In Wellhead Pressure (psi)						

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 01	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				
Rig Information						
Name	Id	Type	ABS Date	Coast Guard Date		
BETA RIG #2	36006	PLATFORM				
Blowout Preventers						
Preventer	Size	Working Pressure	--- Test Pressure ---			
			Low	High		
Rams	2x5	5000	250	2350		
Annular		5000	250	2350		
Date Commencing Work (mm/dd/yyyy) 19-AUG-2025						
Estimated duration of the operation (days) 7						
Verbal Approval Information						
Official			Date (mm/dd/yyyy)			
Questions						
Number	Question	Response	Response Text			
A	Is H2S present in the well? If yes, then comment on the inclusion of a Contingency Plan for this operation.	NO				
B	Is this proposed operation the only lease holding activity for the subject lease? If yes, then comment.	NO				
C	Will all wells in the well bay and related production equipment be shut-in when moving on to or off of an offshore platform, or from well to well on the platform? If not, please explain.	N/A				
D	If sands are to be commingled for this completion, has approval been obtained?	N/A				
E	Will the completed interval be within 500 feet of a block line? If yes, then comment.	NO				
F	For permanent abandonment, will casings be cut 15 feet below the mudline? If no, then comment.	N/A				
G	Will you ensure well-control fluids, equipment, and operations be designed, utilized, maintained, and/or tested as necessary to control the well in foreseeable conditions and circumstances, including subfreezing conditions?	YES				

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 01	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				

Questions

Number	Question	Response	Response Text
H	Will digital BOP testing be used for this operation? If "yes", state which version in the comment box?	NO	
I	Is this APM being submitted to remediate sustained casing pressure (SCP)? If "yes," please specify annulus in the comment box. If you have been given a departure/denial for SCP, include in the attachments.	NO	
J	Are you pulling tubulars and/or casing with a crane? If "YES" have documentation on how you will verify the load is free per API RP 2D. This documentation must be maintained by the lessee at the lessee's field office.	NO	
K	Will the proposed operation be covered by an EPA Discharge Permit? (Please provide permit number comments for this question).	N/A	
L	Will you be using multiple size work string/ tubing/coil tubing/snubbing/wireline? If yes, attach a list of all sizes to be used including the size, weight, and grade.	NO	
M	For both surface and subsea operations, are you utilizing a dynamically positioned vessel and/or non-bottom supported vessel at any time during this operation?	NO	

ATTACHMENTS

File Type	File Description
pdf	Directional Survey
pdf	Workover Program
pdf	Third Party Engineering Review v1
pdf	Halliburton iCem Report v2 REVISED
pdf	Third Party Engineering Review V2 REVISED
pdf	Halliburton iCem Report v1
pdf	Proposed Wellbore Diagram v1
pdf	Workover Program v2 REVISED
pdf	Well Test Information

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 01	BP 00	Type Development
Application Status		Approved Operator 03126 Beta Operating Company, LLC				
pdf Proposed Wellbore Schematic						
pdf Current Wellbore Schematic						
pdf BOP1						
pdf BOP2						
pdf BOP3						
pdf BOP cert						
pdf Well C-61 CER						
CONTACTS						
Name		Rebecca Altemus				
Company		Beta Operating Company, LLC				
Phone Number		832-408-8652				
E-mail Address		rebecca.altemus@amplifyenergy.com				
Contact Description						

CERTIFICATION: I certify that information submitted is complete and accurate to the best of my knowledge. I understand that making a false statement may subject me to ci

Name and Title	Date
Rebecca Altemus, Senior Staff Reservoir Eng	30-JUL-2025

PAPERWORK REDUCTION ACT OF 1995 (PRA) STATEMENT: The PRA (44 U.S.C. 3501 et seq. Requires us to inform you that we collect this information to obtain knowledge of equipment and procedures to be used in drilling operations. MMS uses the information to evaluate and approve or disapprove the adequacy of the equipment and/or procedures to safely perform the proposed drilling operation. Responses are mandatory (43 U.S.C. 1334). Proprietary data are covered under 30 CFR 250.196. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB Control Number. Public reporting burden for this form is estimated to average 11/4 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to the Information Collection Clearance Officer, Mail Stop 4230, Minerals Management Service, 1849 C Street, N.W., Washington, DC 20240.

Application for Permit to Modify (APM)

Lease P00301 Area LB Block 6488 Well Name C061 ST 01 BP 00 Type Development
Application Status Approved Operator 03126 Beta Operating Company, LLC

Variances Requested for this Permit

Variance Status:	DENIED
Variance Type:	Alternate Compliance
Variance Title:	Location of cement retainer and placement of cement
Regulation Number:	30 CFR 250.1715
Oper. Justification:	Amplify requests to set the 9-5/8" cement retainer at +/- 3900' ELM and pump 59 bbls of cement below the retainer. No cement is desired above the retainer as it will be the base of the Whipstock for the sidetrack. The retainer will be used as the correlated base for setting the whipstock assembly ensuring collars are avoided. Also, Amplify wants as deep a Kick Off point as possible for frac gradient purposes; adding cement above the retainer would create a more shallow Kick Off Point.
Variance Date:	
BSEE Decision Remarks:	Comply with the requirement of 30 CFR 250.1715(4)(ii) by setting at least 50 feet of cement on top of the proposed retainer.
	31-JUL-25

Application for Permit to Modify (APM)

Lease P00301 **Area** LB **Block** 6488 **Well Name** C061 **ST** 01 **BP** 00 **Type** Development
Application Status Approved **Operator** 03126 Beta Operating Company, LLC

Existing Variances

No previously approved variances exist for this permit

Application for Permit to Modify (APM)

Lease P00301 Area LB Block 6488 Well Name C061 ST 01 BP 00 Type Development
Application Status Approved Operator 03126 Beta Operating Company, LLC

Reviews

Review:	APM - District Production Engineering Review
Sent:	23-JUL-25
Review Started:	23-JUL-25
Review Finished:	23-JUL-25
Info Adequate:	Y
Review Remarks:	

Review:	BOP Control System Drawing Review
Sent:	23-JUL-25
Review Started:	23-JUL-25
Review Finished:	23-JUL-25
Info Adequate:	Y
Review Remarks:	

Review:	Determination of NEPA Adequacy
Sent:	23-JUL-25
Review Started:	23-JUL-25
Review Finished:	23-JUL-25
Info Adequate:	Y
Review Remarks:	