

Application for Permit to Modify (APM)

Lease	P00441	Area	SM	Block	6374	Well Name	A026	ST	00	BP	00	Type	Development
Application Status	Approved			Operator	03280 Freeport-McMoRan Oil & Gas LLC								
Pay.gov				Agency				Pay.gov					
Amount:	\$145.00			Tracking ID:	EWL-APM-256732			Tracking ID:	27OUIINRF				
General Information													
API	560452008200			Approval Dt	27-AUG-2025			Approved By	Junaid Ashfaq				
Submitted Dt	19-JUN-2025			Well Status	Completed			Water Depth	242				
Surface Lease	P00441			Area	SM			Block	6374				
Approval Comments													
Correction Narrative													
Permit Primary Type Abandonment Of Well Bore													
Permit Subtype(s)													
Temporary Abandonment													
<input checked="" type="checkbox"/> Proposed or <input type="checkbox"/> Completed Work													
Operation Description													
Procedural Narrative													
Please refer to attached procedures and WBss.													
Subsurface Safety Valve													
Type Installed N/A													
Feet below Mudline													
Maximum Anticipated Surface Pressure (psi) 1535													
Shut-In Tubing Pressure (psi) 0													
Maximum Anticipated Wellhead Pressure (psi)													
Shut-In Wellhead Pressure (psi)													
Rig Information													
Name				Id		Type		ABS Date		Coast Guard Date			
* HYDRAULIC WORKOVER UNIT				47935		Hydraulic Workove:		31-DEC-2049		31-DEC-2049			
Blowout Preventers													
								--- Test Pressure ---					
Preventer		Size		Working Pressure		Low		High					
Rams		21.25		5000		250		2100					
Annular				5000		250		1400					
Wireline Luber				5000				2100					
Date Commencing Work (mm/dd/yyyy) 01-AUG-2025													
Estimated duration of the operation (days) 14													
Verbal Approval Information													
Official								Date (mm/dd/yyyy)					
Questions													
Number				Question		Response		Response Text					

## Application for Permit to Modify (APM)

<b>Lease</b> P00441	<b>Area</b> SM	<b>Block</b> 6374	<b>Well Name</b> A026	<b>ST</b> 00	<b>BP</b> 00	<b>Type</b> Development
<b>Application Status</b> Approved		<b>Operator</b> 03280 Freeport-McMoRan Oil & Gas LLC				

### Questions

Number	Question	Response	Response Text
A	Is H2S present in the well? If yes, then comment on the inclusion of a Contingency Plan for this operation.	YES	Previously submitted
B	Is this proposed operation the only lease holding activity for the subject lease? If yes, then comment.	NO	
C	Will all wells in the well bay and related production equipment be shut-in when moving on to or off of an offshore platform, or from well to well on the platform? If not, please explain.	YES	
D	If sands are to be commingled for this completion, has approval been obtained?	N/A	
E	Will the completed interval be within 500 feet of a block line? If yes, then comment.	N/A	
F	For permanent abandonment, will casings be cut 15 feet below the mudline? If no, then comment.	N/A	
G	Will you ensure well-control fluids, equipment, and operations be designed, utilized, maintained, and/or tested as necessary to control the well in foreseeable conditions and circumstances, including subfreezing conditions?	YES	
H	Will digital BOP testing be used for this operation? If "yes", state which version in the comment box?	YES	OTC Greenlight Version 2.0
I	Is this APM being submitted to remediate sustained casing pressure (SCP)? If "yes," please specify annulus in the comment box. If you have been given a departure/denial for SCP, include in the attachments.	YES	SCP, 9-5/8" = 298 psi and 13-3/8" casing = 31 psi

## Application for Permit to Modify (APM)

<b>Lease</b> P00441	<b>Area</b> SM	<b>Block</b> 6374	<b>Well Name</b> A026	<b>ST</b> 00	<b>BP</b> 00	<b>Type</b> Development
<b>Application Status</b> Approved		<b>Operator</b> 03280 Freeport-McMoRan Oil & Gas LLC				

### Questions

Number	Question	Response	Response Text
J	Are you pulling tubulars and/or casing with a crane? If "YES" have documentation on how you will verify the load is free per API RP 2D. This documentation must be maintained by the lessee at the lessee's field office.	NO	
K	Will the proposed operation be covered by an EPA Discharge Permit? (Please provide permit number comments for this question).	N/A	
L	Will you be using multiple size work string/ tubing/coil tubing/snubbing/wireline? If yes, attach a list of all sizes to be used including the size, weight, and grade.	YES	Drillpipe - 3½", 13.3, S-135 Electric Line - 7/32", 0.092, GEIPS
M	For both surface and subsea operations, are you utilizing a dynamically positioned vessel and/or non-bottom supported vessel at any time during this operation?	NO	

### ATTACHMENTS

File Type	File Description
pdf	ISS degasser Calc
pdf	Equipment Layout
pdf	Test Schematic
pdf	Test Procedures
pdf	Rig Up Analysis
pdf	13.375in Cmt Diff Analysis Calc
pdf	Cement Bond Index, Well Cementing, E.B. Nelson
pdf	Class G Cmt Compressive Strength & Shear Bond Strength
pdf	Procedures
pdf	Narrative Ops
pdf	Well A-26 CER
pdf	Rig/Coil Tubing/Snubbing Unit BOP Schematic
pdf	Proposed Wellbore Schematic
pdf	Current Wellbore Schematic

### CONTACTS

<b>Name</b>	Nancy Rodriguez
<b>Company</b>	Freeport-McMoRan Oil & Gas LLC

Application for Permit to Modify (APM)

Lease	P00441	Area	SM	Block	6374	Well Name	A026	ST	00	BP	00	Type	Development
Application Status	Approved			Operator	03280 Freeport-McMoRan Oil & Gas LLC								
<div>Phone NumberCONTACTS</div> <div>E-mail Address</div> <div>Contact Description</div> <div>281-539-7640</div> <div>nrodrigu@fmi.com</div> <div>Aaron Novy</div> <div>Freeport-McMoRan Oil &amp; Gas LLC</div> <div>979-739-1679</div> <div>anovy@fmi.com</div>													

CERTIFICATION: I certify that information submitted is complete and accurate to the best of my knowledge. I understand that making a false statement may subject me to ci

Name and Title	Date
Nancy Rodriguez, Regulatory Supervisor	19-JUN-2025

PAPERWORK REDUCTION ACT OF 1995 (PRA) STATEMENT: The PRA (44 U.S.C. 3501 et seq. Requires us to inform you that we collect this information to obtain knowledge of equipment and procedures to be used in drilling operations. MMS uses the information to evaluate and approve or disapprove the adequacy of the equipment and/or procedures to safely perform the proposed drilling operation. Responses are mandatory (43 U.S.C. 1334). Proprietary data are covered under 30 CFR 250.196. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB Control Number. Public reporting burden for this form is estimated to average 11/4 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to the Information Collection Clearance Officer, Mail Stop 4230, Minerals Management Service, 1849 C Street, N.W., Washington, DC 20240.

## Application for Permit to Modify (APM)

Lease P00441    Area SM    Block 6374    Well Name A026    ST 00    BP 00    Type Development  
Application Status Approved    Operator 03280 Freeport-McMoRan Oil & Gas LLC

### Variances Requested for this Permit

Variance Status: APPROVED  
Variance Type: Alternate Compliance  
Variance Title: TA operations  
Regulation Number: 30 CFR 250.1715(a)(4)  
Oper. Justification: FMOG requests an Alternate Compliance to 30 CFR 250.1715(a)(4)(ii) in setting the 13-3/8" inflatable bridge plug within less than 50' of the 9-5/8" stub end at 682' MD due to only milling a 20' window in the 9-5/8" casing to accommodate 10' of cement in the 13-3/8" casing.  
Variance Date:  
BSEE Decision Remarks: adequate coverage  
27-AUG-25

Variance Status: APPROVED  
Variance Type: Departure  
Variance Title: TA operations  
Regulation Number: 30 CFR 250.1715(a)(6)  
Oper. Justification: #1. FMOG requests a departure to 30 CFR 250.1715(a)(6) to section mill a window of sufficient length in the 9-5/8" casing to accommodate setting a mechanical barrier and spot less than 200' of cement in the 13-3/8" casing to isolate the 9-5/8" x 13-3/8" hole section. FMOG will mill a 20' window in the 9-5/8" casing and set 10' of cement on the mechanical barrier set in the 13-3/8" casing. . The departure is requested for the following justification: o Milling a window in the 9-5/8" casing sufficient enough to accommodate a mechanical barrier and 200' of cement in the 13-3/8" casing is not necessary to accomplish the primary objective of: - Isolating the 9-5/8" x 13-3/8" hole section, by setting an inflatable bridge plug in the 13-3/8" casing, thus isolating the 9-5/8" casing and 13-3/8" casing. - The more exposure the section tool has to cuttings from the 9-5/8" casing could limit the success of pulling the section tool back to surface. o At 65% cement bond strength, which is considered the pessimistic case for cement bond in an open hole situation, of the 15.6 ppg Class G Cement, the differential pressure of 10' of cement inside the 13-3/8", 61 ppf, J-55 casing is 5,235 psi. The MASP of the well is 1,535 psi, which is the worst-case exposure to the 13-3/8" casing in the event of reservoir repressuring or channeling pressure. 5,235 psi > 1,535 psi. Please see the attached document labeled, Cement Bond Strength Differential Analysis for 10' of 15.6 ppg Class G Cement in the 13-3/8" Casing. o As per procedure FMOG is performing the following procedure to ensure that the inflatable packer is holding pressure from below the inflatable packer prior to performing cementing operations. - Manufacturer pull test on the inflatable packer once the packer is set against the 13-3/8" casing ID. -

Application for Permit to Modify (APM)

Lease P00441    Area SM    Block 6374    Well Name A026    ST 00    BP 00    Type Development  
Application Status Approved    Operator 03280 Freeport-McMoRan Oil & Gas LLC

BSEE Decision Remarks:		Bubble test of the packer for 90 minutes. - Release from packer. - Bubble test of the packer for 90 minutes. - FMOG will subsequently bubble test the 13-3/8" casing from surface after the packer and cement are set.  Pull test and bubble test more than adequately cover the window  27-AUG-25
Variance Status:		APPROVED
Variance Type:		Alternate Compliance
Variance Title:		TA operations
Regulation Number:		30 CFR 250.737(b)(1)
Oper. Justification:		FMOG requests an Alternate Compliance to 30 CFR 250.737(b)(1) and CFR 250.737(b)(2) to only test the inside of the choke and kill side outlet valves.
<del>BSEE Decision:</del> Remarks:		allowable  27-AUG-25
Variance Status:		APPROVED
Variance Type:		Alternate Compliance
Variance Title:		TA operations
Regulation Number:		30 CFR 250.737(b)(2)
Oper. Justification:		FMOG requests an Alternate Compliance to 30 CFR 250.737(b)(1) and CFR 250.737(b)(2) to only test the inside of the choke and kill side outlet valves.
<del>BSEE Decision:</del> Remarks:		adequate coverage  27-AUG-25
Variance Status:		APPROVED
Variance Type:		Alternate Compliance
Variance Title:		Digital BOP testing
Regulation Number:		30 CFR 250.737(c)
Oper. Justification:		FMOG requests an alternate compliance to 30 CFR 250.737(c) to use BOPE testing software, OTC Greenlight Version 2.0.21, in a predictive mode.
<del>BSEE Decision:</del> Remarks:		widely accepted  27-AUG-25

**Application for Permit to Modify (APM)**

**Lease** P00441    **Area** SM    **Block** 6374    **Well Name** A026    **ST** 00    **BP** 00    **Type** Development  
**Application Status** Approved    **Operator** 03280 Freeport-McMoRan Oil & Gas LLC

**Existing Variances**

No previously approved variances exist for this permit

## Application for Permit to Modify (APM)

**Lease** P00441    **Area** SM    **Block** 6374    **Well Name** A026    **ST** 00    **BP** 00    **Type** Development  
**Application Status** Approved    **Operator** 03280 Freeport-McMoRan Oil & Gas LLC

### Reviews

Review:	APM - District Production Engineering Review
Sent:	23-JUN-25
Review Started:	23-JUN-25
Review Finished:	23-JUN-25
Info Adequate:	Y
Review Remarks:	
Review:	BOP Control System Drawing Review
Sent:	23-JUN-25
Review Started:	23-JUN-25
Review Finished:	23-JUN-25
Info Adequate:	Y
Review Remarks:	
Review:	CTU/Snubbing Control System Review
Sent:	23-JUN-25
Review Started:	23-JUN-25
Review Finished:	23-JUN-25
Info Adequate:	Y
Review Remarks:	
Review:	Determination of NEPA Adequacy
Sent:	23-JUN-25
Review Started:	23-JUN-25
Review Finished:	23-JUN-25
Info Adequate:	Y
Review Remarks:	
Review:	Regional Concurrence Departure Review
Sent:	26-AUG-25
Review Started:	27-AUG-25
Review Finished:	27-AUG-25
Info Adequate:	Y
Review Remarks:	
Review:	Regional Concurrence Review
Sent:	09-JUL-25
Review Started:	09-JUL-25
Review Finished:	09-JUL-25
Info Adequate:	Y
Review Remarks:	



Application for Permit to Modify (APM)

Lease P00441    Area SM    Block 6374    Well Name A026    ST 00    BP 00    Type Development  
Application Status Approved    Operator 03280 Freeport-McMoRan Oil & Gas LLC

Reviews

Review:	Regional Concurrence Review
Sent:	09-JUL-25
Review Started:	09-JUL-25
Review Finished:	09-JUL-25
Info Adequate:	Y
Review Remarks:	