

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 02	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				
Pay.gov Amount: \$145.00		Agency Tracking ID: EWL-APM-258791		Pay.gov Tracking ID: 27T6CQ4T		
General Information						
API 043122016602		Approval Dt 19-NOV-2025		Approved By Bethram Ofole		
Submitted Dt 18-NOV-2025		Well Status Completed		Water Depth 700		
Surface Lease P00301		Area LB		Block 6488		
Approval Comments						
Conditions of Approval 1. All operations must be conducted in accordance with the OCS Lands Act (OCSLA), the lease terms and stipulations, the regulations of 30 CFR Part 250, Notices to Lessees and Operators (NTLs), the approved (revised) Application for Permit to Modify (APM/RPM), and any written instructions or orders of the District Manager or its designee. 2. A copy of this permit (including all attachments) must be kept on site and made available to inspectors upon request during the permitted operation. 3. All pressure-containing equipment must be tested to the approved permitted pressure and recorded on the daily operations report. If well pressures exceed the SITP/MASP stated in the approved permit, the equipment in use must be tested at a minimum to the new observed pressure. The District Manager or its designee must be immediately notified of this pressure change, and an RPM must be submitted to document the change. 4. Notify the Permitting Section at least 72 hours in advance of beginning these approved operations AND of any required BOP tests AND of any plug testing or tagging. You MUST NOT proceed with these operations until an inspector arrives to witness the testing OR the Permitting Section Chief, or their designee waives the witnessing. 5. Well Activity Reports (WARs) are due by noon every Wednesday.						
Correction Narrative						
Permit Primary Type Enhance Production						
Permit Subtype(s) Acidize						
☒ Proposed or ☐ Completed Work						
Operation Description CT / Acid Job						
Procedural Narrative						
Subsurface Safety Valve Type Installed SCSSV Feet below Mudline 195 Maximum Anticipated Surface Pressure (psi) 1400 Shut-In Tubing Pressure (psi) Maximum Anticipated Wellhead Pressure (psi) 1400 Shut-In Wellhead Pressure (psi)						
Rig Information						
Name	Id	Type	ABS Date	Coast Guard Date		

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 02	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				

BETA RIG #1 36007 PLATFORM

Blowout Preventers

Preventer	Size	Working Pressure	--- Test Pressure ---	
			Low	High
Rams	2x5	5000	250	2350
Annular		5000	250	2350
Coil Tubing		10000	250	2350

Date Commencing Work (mm/dd/yyyy) 19-NOV-2025

Estimated duration of the operation (days) 10

Verbal Approval Information

Official **Date (mm/dd/yyyy)**

Questions

Number	Question	Response	Response Text
A	Is H2S present in the well? If yes, then comment on the inclusion of a Contingency Plan for this operation.	NO	
B	Is this proposed operation the only lease holding activity for the subject lease? If yes, then comment.	NO	
C	Will all wells in the well bay and related production equipment be shut-in when moving on to or off of an offshore platform, or from well to well on the platform? If not, please explain.	N/A	
D	If sands are to be commingled for this completion, has approval been obtained?	N/A	
E	Will the completed interval be within 500 feet of a block line? If yes, then comment.	NO	
F	For permanent abandonment, will casings be cut 15 feet below the mudline? If no, then comment.	N/A	
G	Will you ensure well-control fluids, equipment, and operations be designed, utilized, maintained, and/or tested as necessary to control the well in foreseeable conditions and circumstances, including subfreezing conditions?	YES	

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 02	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				

Questions

Number	Question	Response	Response Text
H	Will digital BOP testing be used for this operation? If "yes", state which version in the comment box?	NO	
I	Is this APM being submitted to remediate sustained casing pressure (SCP)? If "yes," please specify annulus in the comment box. If you have been given a departure/denial for SCP, include in the attachments.	NO	
J	Are you pulling tubulars and/or casing with a crane? If "YES" have documentation on how you will verify the load is free per API RP 2D. This documentation must be maintained by the lessee at the lessee's field office.	NO	
K	Will the proposed operation be covered by an EPA Discharge Permit? (Please provide permit number comments for this question).	YES	CAG2800000
L	Will you be using multiple size work string/ tubing/coil tubing/snubbing/wireline? If yes, attach a list of all sizes to be used including the size, weight, and grade.	NO	
M	For both surface and subsea operations, are you utilizing a dynamically positioned vessel and/or non-bottom supported vessel at any time during this operation?	NO	

ATTACHMENTS

File Type	File Description
pdf	Proposed Wellbore Schematic
pdf	Current Wellbore Schematic
pdf	Procedure
pdf	1. TPS 930 Power Pack
pdf	2. C-61 Accumulator Sizing Calculator Method
pdf	6. EH 3.06 10K BOP
pdf	5. Dual Flapper Check Valve
pdf	4. COC Offshore Stripper
pdf	3. Stripper Manual

Application for Permit to Modify (APM)

Lease P00301	Area LB	Block 6488	Well Name C061	ST 02	BP 00	Type Development
Application Status Approved		Operator 03126 Beta Operating Company, LLC				
pdf C61 Directional Final Surveys						
pdf Eureka BOP Data 1 of 4						
pdf Eureka BOP Data 2 of 4						
pdf Eureka BOP Data 3 of 4						
pdf Eureka BOP Data 4 of 4						
pdf Well C-61 CER						
CONTACTS						
Name	Kelley Pisciola					
Company	Beta Operating Company, LLC					
Phone Number	281-758-3388					
E-mail Address	kelley.pisciola@jccteam.com					
Contact Description	Dena Rodriguez Beta Operating Company, LLC 281-578-3388 dena.rodriguez@jccteam.com					

CERTIFICATION: I certify that information submitted is complete and accurate to the best of my knowledge. I understand that making a false statement may subject me to ci

Name and Title

Date

Kelley Pisciola, VP Federal Regulatory

18-NOV-2025

PAPERWORK REDUCTION ACT OF 1995 (PRA) STATEMENT: The PRA (44 U.S.C. 3501 et seq. Requires us to inform you that we collect this information to obtain knowledge of equipment and procedures to be used in drilling operations. MMS uses the information to evaluate and approve or disapprove the adequacy of the equipment and/or procedures to safely perform the proposed drilling operation. Responses are mandatory (43 U.S.C. 1334). Proprietary data are covered under 30 CFR 250.196. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB Control Number. Public reporting burden for this form is estimated to average 11/4 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to the Information Collection Clearance Officer, Mail Stop 4230, Minerals Management Service, 1849 C Street, N.W., Washington, DC 20240.

Application for Permit to Modify (APM)

Lease P00301 **Area** LB **Block** 6488 **Well Name** C061 **ST** 02 **BP** 00 **Type** Development
Application Status Approved **Operator** 03126 Beta Operating Company, LLC

Variances Requested for this Permit

Application for Permit to Modify (APM)

Lease P00301 **Area** LB **Block** 6488 **Well Name** C061 **ST** 02 **BP** 00 **Type** Development
Application Status Approved **Operator** 03126 Beta Operating Company, LLC

Existing Variances

No previously approved variances exist for this permit

Application for Permit to Modify (APM)

Lease P00301 Area LB Block 6488 Well Name C061 ST 02 BP 00 Type Development
Application Status Approved Operator 03126 Beta Operating Company, LLC

Reviews

Review:	APM - District Production Engineering Review
Sent:	19-NOV-25
Review Started:	19-NOV-25
Review Finished:	19-NOV-25
Info Adequate:	Y
Review Remarks:	

Review:	BOP Control System Drawing Review
Sent:	19-NOV-25
Review Started:	19-NOV-25
Review Finished:	19-NOV-25
Info Adequate:	Y
Review Remarks:	

Review:	CTU/Snubbing Control System Review
Sent:	19-NOV-25
Review Started:	19-NOV-25
Review Finished:	19-NOV-25
Info Adequate:	Y
Review Remarks:	

Review:	Determination of NEPA Adequacy
Sent:	18-NOV-25
Review Started:	18-NOV-25
Review Finished:	18-NOV-25
Info Adequate:	Y
Review Remarks:	