

Application for Permit to Modify (APM)

Lease P00166	Area LA	Block 6660	Well Name A001	ST 01	BP 00	Type Development
Application Status Approved		Operator 02531 DCOR, L.L.C.				
Pay.gov Amount:		Agency Tracking ID: 77156721886		Pay.gov Tracking ID: 27RE7RUM		
General Information						
API 043112001301		Approval Dt 06-FEB-2026		Approved By Bethram Ofole		
Submitted Dt 15-JAN-2026		Well Status Completed		Water Depth 154		
Surface Lease P00166		Area LA		Block 6660		
Approval Comments						
Conditions of Approval 1)All operations must be conducted in accordance with the OCS Lands Act (OCSLA), the lease terms and stipulations, the regulations of 30 CFR Part 250, Notices to Lessees and Operators (NTLs), the approved (revised) Application for Permit to Modify (APM/RPM), and any written instructions or orders of the District Manager or their designee. 2)A copy of this permit (including all attachments) must be kept on location and made available to inspectors upon request during the permitted operation. 3)A revised PE certification is required if: .The plug type changes in any way, including changes in cement properties. .Any plug's base setting depth (even those not required per §250.1715) changes by ±100' TVD. .The pressure test changes on any plug. .Less cement is to be pumped. .More cement is to be pumped to isolate a hydrocarbon zone not anticipated in the original permit. .A remedial cement job is required that was not included in the original permit. .Any plug change that causes deviation from the §250.1715 table. You must have a PE certify these changes prior to performing the operations. A revised permit with the PE certification must be submitted to this office within 72 hours. 4)While conducting operations, you must have current OSFR coverage for the lease (if applicable). If the lease's OSFR coverage will expire during OCS operations, you must submit an RPM to include the updated OSFR coverage to BSEE prior to the expiration date. 5)If well pressures exceed the permitted MASP/SITP pressures: The well control equipment in use must be tested to at least the new observed pressure plus 500 psi. .The appropriate District must be immediately notified of these pressure changes. .An RPM must be submitted to document the change. .If utilizing wireline, the wireline lubricator must be tested to equal or greater than the new observed pressure. 6)High-pressure blind shear ram close capability must be available from all BOP control panels. Each panel must be clearly marked to indicate that the accumulator system's high-pressure side is required for closing and shearing the drill pipe with the blind-shear rams. If the high-pressure bypass selector valve is not available at all BOP control panels, the accumulator system must be always set to the high-pressure position, except during pressure and function testing. 7)In the event of BOP system failure or leak, you must immediately contact the District Office and receive approval from the District Manager prior to resuming operations. A revised permit will be required to document third-party verification that the BOP is fit for service and will operate under the conditions in which it will be used. 8)At the end of this operation, a tree or dry hole tree must be installed and tested for the purpose of monitoring all non-structural casing annuli that are tied back to the surface.						

Application for Permit to Modify (APM)

Lease P00166	Area LA	Block 6660	Well Name A001	ST 01	BP 00	Type Development
Application Status Approved		Operator 02531 DCOR, L.L.C.				
9) Notify the permitting section at least 72 hours prior to beginning the initial test to allow BSEE representative(s) the opportunity to witness the testing, in accordance with 30 CFR 250.737(d)(2)(ii). If BSEE representative(s) are unable to witness the testing, you must submit the initial test results to the permitting section within 72 hours after completion of the tests. 10) Any casing or annuli that fail a pressure/bubble test must be reported and remediated. 11) WARs are due no later than noon every Wednesday.						
Correction Narrative						
Permit Primary Type Abandonment Of Well Bore						
Permit Subtype(s)						
Temporary Abandonment						
☒ Proposed or ☐ Completed Work						
Operation Description						
To be TA'd with zonal isolation plug, liner top plug, additional cement plugs across confining shales, cement eval log, if possible prod csg cut & pulled, if so a stub plug, and a surface plug.						
Procedural Narrative						
For zonal isolation plug, if injectivity into the perfs is established, a 5-1/2" cement retainer will be utilized in the liner. Cement will be pumped through and on top of retainer. If no injectivity is established, a CIBP with cement on top will instead be utilized.						
A cement evaluation log will be run in the 5-1/2" and 7" to assess the cement integrity, and evaluated to assess if the top section of 7" casing can be cut & pulled.						
Cement will be pumped across the 5-1/2" liner top and across confining layers (CLs) of shale.						
Depending on the cement evaluation log, CL shales will be isolated by Options: 1) the 5-1/2" liner top may be cut & pulled to expose CL1 for a cement plug; or 2) cement plug(s) inside the 7"; or 3) perforating 7", and cement squeezing the annulus across CL(s); or 4) section milling the 7" casing across CL(s), underreaming the interval, and installing an inflatable bridge plug and a cement plug.						
If the 7" was cut and pulled above the 10-3/4" shoe, a casing stub cement plug will be installed. Lastly a surface cement plug will be placed.						
Subsurface Safety Valve						
Type Installed N/A						
Feet below Mudline						
Maximum Anticipated Surface Pressure (psi) 1100						
Shut-In Tubing Pressure (psi) 0						
Maximum Anticipated Wellhead Pressure (psi) 300						
Shut-In Wellhead Pressure (psi) 140						
Rig Information						

Application for Permit to Modify (APM)

Lease P00166	Area LA	Block 6660	Well Name A001	ST 01	BP 00	Type Development
Application Status Approved		Operator 02531 DCOR, L.L.C.				
Name * HYDRAULIC WORKOVER UNIT	Id 47935	Type Hydraulic Workover	ABS Date 31-DEC-2049	Coast Guard Date 31-DEC-2049		
Blowout Preventers						
		--- Test Pressure ---				
Preventer	Size	Working Pressure	Low	High		
Rams	13-5/8	5000	250	1600		
Annular		5000	250	1600		
Date Commencing Work (mm/dd/yyyy) 28-MAY-2026						
Estimated duration of the operation (days) 17						
Verbal Approval Information						
Official			Date (mm/dd/yyyy)			
Questions						
Number	Question	Response	Response Text			
A	Is H2S present in the well? If yes, then comment on the inclusion of a Contingency Plan for this operation.	NO				
B	Is this proposed operation the only lease holding activity for the subject lease? If yes, then comment.	NO				
C	Will all wells in the well bay and related production equipment be shut-in when moving on to or off of an offshore platform, or from well to well on the platform? If not, please explain.	YES				
D	If sands are to be commingled for this completion, has approval been obtained?	N/A				
E	Will the completed interval be within 500 feet of a block line? If yes, then comment.	N/A				
F	For permanent abandonment, will casings be cut 15 feet below the mudline? If no, then comment.	NO	Conductor to be removed at a later date.			
G	Will you ensure well-control fluids, equipment, and operations be designed, utilized, maintained, and/or tested as necessary to control the well in foreseeable conditions and circumstances, including subfreezing conditions?	YES				

Application for Permit to Modify (APM)

Lease P00166	Area LA	Block 6660	Well Name A001	ST 01	BP 00	Type Development
Application Status Approved		Operator 02531 DCOR, L.L.C.				

Questions

Number	Question	Response	Response Text
H	Will digital BOP testing be used for this operation? If "yes", state which version in the comment box?	NO	
I	Is this APM being submitted to remediate sustained casing pressure (SCP)? If "yes," please specify annulus in the comment box. If you have been given a departure/denial for SCP, include in the attachments.	YES	7" x 10-3/4" annulus
J	Are you pulling tubulars and/or casing with a crane? If "YES" have documentation on how you will verify the load is free per API RP 2D. This documentation must be maintained by the lessee at the lessee's field office.	NO	
K	Will the proposed operation be covered by an EPA Discharge Permit? (Please provide permit number comments for this question).	YES	Permit no. CAGZ800000. Discharge not planned.
L	Will you be using multiple size work string/ tubing/coil tubing/snubbing/wireline? If yes, attach a list of all sizes to be used including the size, weight, and grade.	YES	Sizes listed / detailed in Job Plan pp. 3-4
M	For both surface and subsea operations, are you utilizing a dynamically positioned vessel and/or non-bottom supported vessel at any time during this operation?	NO	

ATTACHMENTS

File Type	File Description
pdf	A-1 BOPE Shear Test
pdf	A-1 BOPE Shear Test of WL
pdf	A-1 BOPE Shear Test of Pipe & Sucker Rod
pdf	A-1 BOPE PE Verification
pdf	Well A-01 CER
pdf	Proposed Wellbore Schematic
pdf	Current Wellbore Schematic
pdf	A-1 Proposed WBD Surface Plug Options
pdf	A-1 APM Payment Confirmation

Application for Permit to Modify (APM)

Lease P00166	Area LA	Block 6660	Well Name A001	ST 01	BP 00	Type Development
Application Status Approved		Operator 02531 DCOR, L.L.C.				
pdf A-1 Directional Survey						
pdf A-1 Job Plan						
pdf A-1 Job Plan PE Certification						
CONTACTS						
Name		Scott Lavan				
Company						
Phone Number		805-212-2289				
E-mail Address		slavan@dcorllc.com				
Contact Description		Tyson Holder				
		DCOR, L.L.C.				
		805-320-7111				
		tholder@dcorllc.com				

CERTIFICATION: I certify that information submitted is complete and accurate to the best of my knowledge. I understand that making a false statement may subject me to c

Name and Title	Date
Scott Lavan, Sr. Engineer	15-JAN-2026

PAPERWORK REDUCTION ACT OF 1995 (PRA) STATEMENT: The PRA (44 U.S.C. 3501 et seq. Requires us to inform you that we collect this information to obtain knowledge of equipment and procedures to be used in drilling operations. MMS uses the information to evaluate and approve or disapprove the adequacy of the equipment and/or procedures to safely perform the proposed drilling operation. Responses are mandatory (43 U.S.C. 1334). Proprietary data are covered under 30 CFR 250.196. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB Control Number. Public reporting burden for this form is estimated to average 11/4 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to the Information Collection Clearance Officer, Mail Stop 4230, Minerals Management Service, 1849 C Street, N.W., Washington, DC 20240.

Application for Permit to Modify (APM)

Lease P00166 **Area** LA **Block** 6660 **Well Name** A001 **ST** 01 **BP** 00 **Type** Development
Application Status Approved **Operator** 02531 DCOR, L.L.C.

Variances Requested for this Permit

Application for Permit to Modify (APM)

Lease P00166 Area LA Block 6660 Well Name A001 ST 01 BP 00 Type Development
Application Status Approved Operator 02531 DCOR, L.L.C.

Existing Variances

No previously approved variances exist for this permit

Application for Permit to Modify (APM)

Lease P00166 Area LA Block 6660 Well Name A001 ST 01 BP 00 Type Development
Application Status Approved Operator 02531 DCOR, L.L.C.

Reviews

Review:	APM - District Production Engineering Review
Sent:	06-FEB-26
Review Started:	06-FEB-26
Review Finished:	06-FEB-26
Info Adequate:	Y
Review Remarks:	
Review:	BOP Control System Drawing Review
Sent:	06-FEB-26
Review Started:	06-FEB-26
Review Finished:	06-FEB-26
Info Adequate:	Y
Review Remarks:	
Review:	Determination of NEPA Adequacy
Sent:	21-JAN-26
Review Started:	21-JAN-26
Review Finished:	21-JAN-26
Info Adequate:	Y
Review Remarks:	